Assessment of the condition of underground collector lines

situated inside the technological complexes of underground storage facilities

Agenda

- General information
- Reasons , methodology, planning, execution
- Details from inspection
- Results

Underground gas storage Lab

- 30 years of a solid track record
- Located in the south-western part of Slovakia
- Technical infrastructure
 - Central station
 - Dispatching center
 - Compressor fleet including 8 centrifugal compressors
 - Gas metering
 - Piping and gas collector lines
 - Gathering stations and pipelines







Underground gas storage Lab



Gas collector lines at Central station

- 9 gas collector lines for wet or dry gas
- Nominal diameter from 500 to 700 mm
- Design pressure from 40 to 100 bars
- Age from 20 to 25 years
- Length 13 to 140 m
- Installed either at concreted trenches or buried





Reasons for gas collector lines assessment

- Importance for storage facilities operation
- Age in the middle of their life-cycle
- No specific methodology set by authorities
- Unfavoured access as the most are collectors are buried
- No cathodic protection of buried lines within Central station

All these facts represented unacceptable risk, which forced us to set up a project aimed at definition of remaining useful life of gas collector lines

Methodology

1. Pressure tests

- Statement on current status
- Additional stress at spots with wall thickness losses, affected by corrosion or defects
- No prediction of remaining lifetime

2. Non destructive testing (NDT)

- General perspective of collectors conditions
- Data for forecasting useful life and future inspection program
- However, requires an extensive preparation (excavation, modification, cleaning...)

Planning

Specifically tailored inspection program was processed in close cooperation with external suppliers for every gas collector line split into the following:

- Technical program
- Preparation works
 - Excavations
 - Modifications
 - Cleaning
- Inspection
- Data evaluation
- Contingency planning
- Repairs (if needed)





Time schedule

ID Nareu Okolu	20	103	200+			2005		2006	2006		2007	
	p2	p1	pZ	p1	pZ	p1	pZ	p1	p2	p1	pZ	p1
Collectors of 1.stage	8.8.	V			24.8.		1					
² Technical program	8.8	-	27.8.		:						1	
³ Preparation works		20.8.	S D. B.				1				1	
* Inspection			1.10. 🗧 8 1.	. 10 .	1		ŝ			1		1
⁵ Data evaluation			8.11.	28.11.	i		÷.			1	10	
⁶ Repairs	1	8		28.8.	24.8.	1	1	1			- 10	1
⁷ Collectors K 102, K 103		28	. B.		30.7.	9	1	10		1	10	1
⁸ Technical program		2	8.8. 28.	. 10.			÷			1	13	
⁹ Preparation works	1	1	80.10.	17.8.		1	1	1	181	1	18	71
¹⁰ Inspection			Tel.	8.8. 18	.4	9	Ś.	T.				1
¹¹ Data evaluation		<u></u>		1.4.	12.6.		Ś.	- N			-10 -10	
12 Repairs	Ì	1		17.6.	80.7.	1	1	12	10	1		1
13 Collectors K 100, K 101	1			6.4.		R.			12.6.	1		1
1* Technical program		1		6.4.	27.8.	8	Ś.	R			-10 -10	1
¹⁵ Preparation works	1	1		1	1.B.	28.11.	÷.	1		1		1
¹⁶ Inspection	1	1		1	1	1.8.	18.6.	1	11	1		1
¹⁷ Data evaluation	1			1	1	2.6.	16.7.	1	11	1	12	1
¹⁸ Preparation works for repair	1			1			1.B.	28.11.		- Ö	:	1
¹⁹ Repairs		1			1	1	1	1.8.	12.6.	1	1	
²⁰ Collectors K 104, K 105					1		8.10.				2	
²¹ Technical program	1			1	1		8.10.		20.8.		12	1
22 Preparation works	1	i.		1	1	ă –			1	80.4.	8 1.8.	1
²³ Inspection	- i			1	÷.		1	- 10			Ş.B. 2	A. 10,
24 Data evaluation		1			1		1				16.10.	8.12.
²⁵ Preparation works for repair	1			1			1	1			8.12.	28.2
²⁶ Repairs		<u></u>		1	1	ð.	÷.		13			8.8.



Inspection of collectors K 102, K 103



K 102

Nominal diameter 700 mm Length 57 m Nominal pressure 10 MPa

K 103 Nominal diameter 700 mm Length 26 m Nominal pressure 10 MPa

Findings on collectors K 102, K 103

No serious defects were revealed

- Only lamination defects (mill defects), originating from manufacturing process were found
- There were no relevant indications of internal and external corrosion
- There was not an immediate risk for safety of operation
- However, lamination parts were reinforced by installation of 'hot sleeves'
- Based on simulation, safe operation forecasted until year 2025
- The next inspection with assessment planned 2025



Repairing of collectors K 102, K 103







Inspection of collectors K 100, K 101

K 100

Nominal diameter 700 mm Length 136 m Nominal pressure 10 MPa

K 101

Nominal diameter 700 mm Length 105 m Nominal pressure 10 MPa



Inspection of collectors K 100, K 101

- Excavation and preparation for bends' installation
- Inspection of all off-takes
- Material shop preparation
- Modifications of collectors[^] entries
- Ultrasonic in-line inspection by an external company





Inspection of collectors K 100, K 101









Inspection of collectors K 100, K 101





Findings on collectors K 100, K 101

No serious defects were revealed

- Only lamination defects (mill defects), originating from manufacturing process were found
- Lamination parts were reinforced by installation of ´hot sleeves´
- Based on simulation, safe operation forecasted until

year 2015, the next inspection with assessment planned 2015





Findings on collectors K 100, K 101





Analysis of material stress





Repairing of collectors K 100, K 101









Lessons learned

- Gas collector lines installed at concreted trenches were more defected than those buried ones
- No release to releas
- Defects only from the manufacturing process
- No corrosion was detected inside
- Minimal degradation of material

Contacts

Stanislav Rehak,

NAFTA a.s., Naftarska 965 908 45 Gbely Slovakia

mob. +421 905 352795 E-mail: stanislav.rehak@nafta.sk

Anton Misany

NS a.s. Gbely, Naftarska 1413 908 45 Gbely Slovakia

Ladislav Goryl,

NAFTA a.s., Naftarska 965 908 45 Gbely Slovakia mob. +421 905 707987 E-mail: anton.misany@naftastroj.sk

mob. +421 905 843176 E-mail: ladislav.goryl@nafta.sk