

Ishikari LNG receiving terminal

~Operation will be started in Dec. 2012~

September 28th , 2012 Hokkaido gas




Positioning of Ishikari LNG receiving terminal



$\bigcirc 1$ To establish energy supply base

The first large LNG receiving terminal in Hokkaido


LNG terminal in Japan





2 To improve our supply security by diversification of supply sources


In addition to the supply from South, it will be able to supply gas from North to Sapporo and Otaru area.





3 To enhance supply infrastructure for the future demand expansion

It is possible to spread Natural gas in Hokkaido





Outline of


Ishikari LNG receiving terminal







Process Flow Diagram



Coastal tanker



Main equipment

Equip.	Spec.	Remarks	
LNG storage tank	Aboveground Pre-stressed Concrete (180,000kL)	One of the largest aboveground PC tank in Japan	
LNG vaporizer	SEV 40t/h(1MPa) SEV 80t/h(2MPa) SMV 80t/h(2MPa)	The hot water type is adopted in consideration of the sea water temperature in winter	
BOG compressor	Reciprocating type (11,000m3/h × 2)	To utilize the boil off gas from storage tank for city gas.	
LPG storage tank	499 t × 1	To store LPG for calorie adjustment	
Ocean tanker berth	For standard ocean tankers	Capacity of tankers is 19,400m3 ~177,000m3	
Coastal shipping	For coastal shipping	Capacity of tankers is 2,500m3~ 3,500m3	
Lorry shipping	10 lanes	Rating of LNG shipping is 20 ton/h each lane.	
Central Control Center	Control function for all of this terminal	Including a community relation center that is located at 3F	



Construction view of Ishikari LNG receiving terminal




LNG storage tank



Whole view



Inside of tank




Inner wall (yellow)



Starting to water injection for loading test



Berth



Piles with angle



Concrete casting



Bases for unloading arms



Installation of arms





LPG storage tank



Vaporizer(this side) Building for utility. (other side)



Coastal shipping berth & truck scale for lorry





Lorry shipping



BOG comp.



Heavy snowing in winter



Construction schedule

年	2008	2009	2010	2011	2012	2013	
Milestone	 ▼Apr. publication ▼ Construction plan application Storage(Jan.)Other(Jul) Oct. 7th ▼The first ship In operation ▼Dec.1st 						
		Roof A/R ▼Nov.		l DV.	Coastal shipment ▼May		
Sand compaction							
LNG storage tank							
Arch∕civil							
berth							
Mech./Piping							
Elec./inst.							
Start-up							



Thank you for your kind attention.

